

**KANNUR UNIVERSITY**  
[Planning & Development Branch]

PLD/C1/PICO/20579/Water Heater/Students Amenity/2022

Date : 13/02/2023

**NOTICE INVITING QUOTATIONS**

Sealed competitive Quotations are invited from Registered/Authorised firms for the Civil Works for the Installation of Water Heaters in the Guest Room, Amenity Centre, Thavakkara Campus, Kannur University, Kannur - 2.

The Quotations should reach the Registrar, Kannur University, Thavakkara Campus on or before 24/02/2023 at 3.00 pm and will be opened at 3.30 pm on the same day.

**Conditions**

1. The rate should be inclusive of all Taxes and nothing extra shall be admissible over and rate quoted.
2. Payment will be made through account payee Cheque and no advance payment will be sanctioned.
3. Work shall be completed in **2 months** from the date of Agreement.

The Engineering wing of the University shall be contacted during office hours to get details of the work. (Overseer-9048744011, AE-9447888154)

The Registrar, Kannur University reserves the right to reject any of the Quotations or all the Quotations without assigning any reasons whatsoever.

sd/-  
**REGISTRAR(i/c)**

To

1. Notice Board
2. Official Website
3. EE

# KANNUR UNIVERSITY

## QUOTATION SCHEDULE

**Providing water connection for water geyser for using in the guest rooms at room no 405 in amenity centre**

SL. NO	QTY	PARTICULARS	UNIT	RATE INCLUDING ALL TAXES		AMOUNT (RS)
				IN FIGURES (RS)	IN WORDS (RS)	
		<b>1 .Civil Works</b>				
1	12 metre	18.7.4 Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer -in-Charge. Internal work - Exposed on wall 32 mm nominal outer dia pipes	metre			
2	12 metre	50.18.9.14.1 Providing and fixing PVC pipes, fittings including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step PVC solvent cement and testing of joints complete as per direction of Engineer-in-Charge 32 mm dia 10 Kg/cm <sup>2</sup> - External work- Exposed on wall	metre			
3	2 Nos	18.76.1 Cutting holes up to 30x30 cm in walls including making good the same:With common burnt clay F.P.S. ( non modular ) brick	Nos			
4	2 Nos	17.22B Providing and fixing CP Brass Single lever telephonic wall mixer of quality& make as approved by Engineer in charge.(a) 15 mm nominal dia	Nos			
5	2 Nos	18.17.1 Providing and fixing gun metal gate valve with C.I. wheel of approved quality (screwed end) :25 mm nominal bore	Nos			

6	2 Nos	18.19.1.2 Providing and fixing gun metal non-return valve of approved quality (screwed end):25 mm nominal bore Vertical	Nos			
7	4 Nos	18.53.1 Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS: 893115 mm nominal bore	Nos			
		<b>TOTAL</b>				

(Rupees.....Only)

**Signature:**

**Name & Adress of the Quotationer:**

**Date:**

REGISTRAR