

KANNUR UNIVERSITY**QUOTATION SCHEDULE**

NAME OF THE WORK : Civil works in connection with the Installation of water purifiers for admin block and academic block at Kannur University Thavakkara Campus.

LAST DATE OF SUBMISSION:

SL NO	QUANTITY	ITEM DESCRIPTION	UNIT	RATE INCLUDING ALL TAXES		AMOUNT	REMARKS
				RATE IN FIGURES	RATE IN WORDS		
		1 .INSTALLATION OF WATER PURIFIERS IN ADMIN BLOCK					
1	150	50.18.9.3.1 . Providing and fixing PVC pipes includings jointing of pipes with one step PVC solvent cement, trenching,refilling & testing of joints complete as per direction of Engineer in Charge 25 mm dia 12Kfg/cm2	mtr				
2	5	100.59.1 Cutting the bituminous / concrete roads with cutting machine for a minimum depth of 200mm along the sides of proposed alignment of the pipe to be laid without causing any damage to other utilities, including the charges for hire and conveyance of tools and plant, cost of consumables and charges for lighting,watching, ribbon fencing, caution boards, traffice diversion, and as per the direction of departmental officers etc. complete, before carrying out the demolition of bituminous / concrete road by mechanical means and carrying out the excavation.	mtr				
3	0.25	50.4.1.1 Providing and laying in position cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 12.5 mm nominal size) up to floor five level excluding the cost of centering, shuttering,finishing for leveling coarse of floor and roof etc.	cum				

SL NO	QUANTITY	ITEM DESCRIPTION	UNIT	RATE INCLUDING ALL TAXES		AMOUNT	REMARKS
				RATE IN FIGURES	RATE IN WORDS		
4	40	50.18.8.2.1 Providing and fixing PVC pipes, fittings including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step PVC solvent cement and testing of joints complete as per direction of Engineer-in-Charge. Concealed work,including cutting chased and making good the wall etc. 20 mm pipe 12 Kgf/cm2	mtr				
5	6	26.30.1 Drilling suitable holes in reinforced or plain cement concrete with power drivendrill machine to a minimum depth of 100mm upto 200mm in RCC beams, lintels,columns and slabs to introduce steel bars for sunshades/balconies includingfixing the steel bars in position using epoxy resin anchor grout of approvedmake but excluding the cost of reinforcement, all complete as per direction ofEngineer-In-Charge.Upto and including 12mm dia.	holes				
6	3	Providing and fixing gun metal gate valve with C.I. wheel of approved quality (screwed end) :25 mm nominal bore	each				
7	2	18.63 Providing and fixing PTMT angle stop cock 15 mm nominal bore, weighing not less than 85 gms	each				
		2 INSTALATION OF WATER PURIFIER IN ACADAMIC BLOCK					
1	20	50.18.9.3.1 Providing and fixing PVC pipes includings jointing of pipes with one step PVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge 25 mm dia 12Kfg/cm2	mtr				

SL NO	QUANTITY	ITEM DESCRIPTION	UNIT	RATE INCLUDING ALL TAXES		AMOUNT	REMARKS
				RATE IN FIGURES	RATE IN WORDS		
2	20	50.18.8.2.1 Providing and fixing PVC pipes, fittings including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step PVC solvent cement and testing of joints complete as per direction of Engineer-in-Charge. Concealed work,including cutting chased and making good the wall etc. 20 mm pipe 12 Kgf/cm2	mtr				
3	2	18.17.1 Providing and fixing gun metal gate valve with C.I. wheel of approved quality (screwed end) :25 mm nominal bore	each				
4	1	18.63 Providing and fixing PTMT angle stop cock 15 mm nominal bore, weighing not less than 85 gms	each				
TOTAL							

*Rate including GST
(RupeesOnly)

SIGNATURE

Name & Address of the Quotationer

Date

REGISTRAR