

KANNUR UNIVERSITY

PLD/C1/2951/PICO A/Water Purifier/TVKRA/2022

Date ²³11/11/2022

NOTICE INVITING QUOTATIONS

Sealed competitive Quotations are invited from Registered/Authorised firms for the Electrical works with regard to the Installation of Water Purifiers in the Administration block and Academic block at the Thavakkara Campus, Kannur University, Kannur - 2.

The Quotations should reach the Registrar, Kannur University, Thavakkara Campus on or before 02/12/2022 at 3.00 pm and will be opened at 3.30 pm on the same day.

Conditions

1. The rate should be inclusive of all Taxes and nothing extra shall be admissible over and rate quoted.
2. Payment will be made through account payee cheque and no advance payment will be sanctioned.
3. Work shall be completed in 60 days from the date of Agreement.

The Registrar, Kannur University reserves the right to reject any of the Quotations or all the Quotations without assigning any reasons whatever.

Sd/-
REGISTRAR(i/c)

To

1. Notice Board
2. Official Website

KANNUR UNIVERSITY

QUOTATION SCHEDULE

NAME OF THE WORK: ELECTRICAL WIRING WORKS FOR WATER PURIFIERS FOR ACADEMIC BLOCK AND ADMINISTRATION BLOCK BUILDING AT KANNUR UNIVERSITY THAVAKKARA CAMPUS

LAST DATE OF SUBMISSION:

| SL NO | QUANTITY | ITEM DESCRIPTION | UNIT | RATE INCLUDING ALL TAXES | | AMOUNT | REMARKS |
|-------|----------|--|------|--------------------------|---------------|--------|---------|
| | | | | RATE IN FIGURES | RATE IN WORDS | | |
| | | ELECTRICAL WIRING WORKS FOR WATER PURIFIERS FOR ACADEMIC BLOCK AND ADMINISTRATION BLOCK BUILDING AT KANNUR UNIVERSITY THAVAKKARA CAMPUS | | | | | |
| 1 | 80 | Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface / recessed steel/ PVC conduit as required.3 x 2.5 sq. mm | mtr | | | | |
| 2 | 75 | Supplying and fixing of following sizes of medium class PVC conduit along with accessories in surface/ recess including cutting the wall and making good the same in case of recessed conduit as required.20 mm | mtr | | | | |
| 3 | 3 | Supplying and fixing following Modular base & cover plate on existing modular metal boxes etc. as required.3 Module | nos | | | | |
| 4 | 3 | Supply & Fixing the following types/ sizes of boxes suitable for modular accessories in surface/ recess including making good the damages, colour washing etc as required (RoHS compliant)3 module moulded plastic box on surface | nos | | | | |
| 5 | 3 | Supply and Fixing the following modular switches & accessories in the existing front plates and giving necessary connections as required (RoHS compliant)25A SP switch with indicator | nos | | | | |
| 6 | 3 | Supply and Fixing the following modular switches & accessories in the existing front plates and giving necessary connections as required (RoHS compliant)25A 3pin Shuttered socket | nos | | | | |
| | | TOTAL | | | | | |

*Rate including GST

(RupeesOnly)

SIGNATURE

| SL NO | QUANTITY | ITEM DESCRIPTION | UNIT | RATE INCLUDING ALL TAXES | | AMOUNT | REMARKS |
|-------|----------|------------------|------|--------------------------|---------------|--------|---------|
| | | | | RATE IN FIGURES | RATE IN WORDS | | |

Name & Address of the Quotationer

Date

REGISTRAR