



KANNUR UNIVERSITY
(PLANNING AND DEVELOPMENT BRANCH)
NOTICE INVITING TENDERS

PLD/E4/1247/Cabling & Wiring/TVKRA/2023 (I)

30.12.2023

Sealed competitive tenders superscribed as LT CABLE LAYING FROM 62.5 KVA DG SET TO ADMN BUILDING SERVER ROOM AT THAVAKKARA CAMPUS are invited from registered Electrical licensed Contractors/firms.

Sl.No	Name of Work	EMD	TENDER FEE	Time for the completion of work	Defects Liability Period	Last date of submission
1	2	3	4	5	6	7
1	Providing separate cable from 62.5 KVA generator installed in the Sub station to existing server room in second floor of Administrative Building at Thavakkara Campus, Kannur University	Rs.8,752/-	Rs.826/- including GST @ 18%	45 days from the date of Agreement	3 years from the date of completion of work	16-01-2024 3 p m

1. Tender Form can be had from Kannur University Website www.kannuruniversity.ac.in.
2. A sum of Rs.826/- (including GST @18%) towards the cost of Tender form and an amount of Rs.8,752/- as EMD should be remitted separately by way of Demand Draft drawn in favour of Finance Officer, Kannur University, payable at SBI South Bazar Branch, Kannur or Kannur Branch of any other Nationalized or scheduled Bank.
3. The Tenderer should send along with the tender an initial agreement executed and signed in Kerala Stamp Paper of value ₹.200/-
4. The Tenderer shall have valid GST registration and shall furnish a copy of registration certificate along with the tender documents.
5. The successful Tenderer before signing the Agreement and within the period specified in the work order, shall deposit a sum equivalent to 3% of the value of the contract as Performance Guarantee.
6. The rate quoted should be inclusive of GST and all other charges if any. The base rate, GST charges and other charges if any should be furnished separately and nothing extra shall be admissible over and above the rate quoted.

7. Payment will be made through account and no advance payment will be sanctioned
8. Received tenders will be opened on 16-01-2024, 3.30 pm .
9. Details of work can be had from the Planning and Development Branch on all working days up to 5 pm.

The Registrar, Kannur University, reserves the right to reject any of the tenders or all the tenders without assigning any reason whatsoever.



Dr. Joby K Jose
REGISTRAR

2

To

1. Notice Board
2. Website

KANNUR UNIVERSITY

TENDER SCHEDULE

NAME OF THE WORK: LT CABLE LAYING FROM 62.5 KVA DG SET TO ADMIN BUILDING SERVER ROOM AT THAVAKKARA CAMPUS

LAST DATE OF SUBMISSION: 16-01-2024, 3 PM

SL NO	QUANTITY	ITEM DESCRIPTION	UNIT	RATE IN FIGURES	RATE IN WORDS	AMOUNT (Rs)
1	210	Supply and laying of one number PVC insulated and PVC sheathed armoured aluminium power cable of 1.1KV grade of the following sizes in ground including excavation of trench of size 35x75 cm,refilling the trench etc.as required but excluding sand cushioning and protective covering(in ordinary soil). 3.5Cx95 sq mm.	meter			
2	90	Supply and laying and clamping of one number PVC insulated and PVC sheathed armoured aluminium power cable of 1.1KV grade of the following sizes using clamps noted along with the cables,spacing of clamps not exceeding 60 cms,making good the damages,colour washing etc.as required 3.5Cx95 sq mm.	meter			
3	2	Supply and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed /XLPE aluminium conductor cable of 1.1KV grade as required 3.5Cx95 sq mm(45 mm).	nos			
4	3	Supply and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed /XLPE aluminium conductor cable of grade as required 3.5Cx240 sq mm(62 mm).	nos			
5	1	Supply and making straight through joint with cast resin compound including ferrules and other jointing materials for following size of PVC insulated and PVC sheathed /XLPE aluminium conductor cable of 1.1KV grade as required 3.5Cx95 sq mm.	nos			
6	3	Remove and reroute existing cable from Generator Panel to main Panel(3.5Cx240 sq mm Cable).	nos			
7	1	Preparation of drawing and documentation works including inspectorate approval.	unit			
Total Amount						
GST @ 18%						
Grand total						

(RupeesOnly)

SIGNATURE:

Name & Address of the of the Contractor:

Date: